Fire Pre GREATER HYDERABAD MUNICIPAL CORPORATION FIRE PREVENTION WING 00

From:

The Commissioner & Special Officer

Greater Hyderabad Municipal Corporation H.M.C.

Hyderabad.

To: The Correspondent,

M/s. St. Rita High School,

FCI-Widia Colony, Miyapur, Serilingampally, Ranga Reddy District.

C/2021, Date: 18-09-2021. RC.NO: 1129/AD/FPW/GHM

Sir.

Greater Hyderabad Municipal Corporation - Fire Prevention Wing-Multi Storied Sub: Building of M/s. St. Rita High School, FCI-Widia Colony, Miyapur, Serilingampally, Ranga Reddy District - Issuance of FIRE NO OBECTION CERTIFICATE -Regarding.

1.Proceeding Rc.No:5041/B2/97, of the Director General, A.P. State Disaster Response Ref: and Fire Services Department, Dated: 12-03-2010

2. Application No: 546693/2021. Dated: 07-09-2021. M/s. St. Rita High School, FCI-Widia Colony, Miyapur, Serilingampally, Ranga Reddy District.

Under the Power delegated vide reference 1ST Cited the District Fire Officer along with Station Fire Officer, Central Zone have inspected Existing Multi Storied building of M/s. St. Rita High School, FCI-Widia Colony, Miyapur, Serilingampally, Ranga Reddy District on 13-09-2021 and submitted the inspection report.

2) The Builder has constructed the existing Multi- Storied building with Ground + Three Upper Floors with a height of 12.00Mtrs for Educational Occupancy (School). Vide reference 2nd cited, the Management has requested to issue FIRE NO OBJECTION CERTIFICATE and submitted the application along with Checklist and as built Plans.

3) PARTCULARS OF THE BUILDING:

a)	Adress of the building	M/s. St. Rita High School, FCI-Widia Colony, Miyapur, Serilingampally, Ranga Reddy District.			
b)	Built-up area/Height	5400.00 Sq. Mtrs/ 12.00Sq.Mtrs			
c)	No of Blocks / Floors	One/ Ground + Three Upper Floors			
d)	Type of occupancy	Educational Building (B)			
	30				

4) FLOOR WISE DETAILS:

SI. No	Floor	Area in Sq. Meters.	Occupancy	Occupant Load given by the management
1	GROUND FLOOR	1350.00	Educational	60
2	FIRST FLOOR	1350.00	Educational	60 .
3	SECOND FLOOR	1350.00	Educational	60
4	THIRD FLOOR	1350.00	Educational	60
	TOTAL	5400.00	Zaucationar	180

5) MEANS OF ESCAPE:

The builder has provided One Internal staircase with width of 01.25 Mtrs and External staircase 1.15Mtrs. The occupant load as per area is 272.08/4 = 68.02 Nos. and the exit width required is 68.02/25 = 02.72 units of 0.50 Mtrs i.e 01.36Mtrs and exit width required as per occupant load given by the management is 50/25 = 02.00 units of 0.50meters i.e. 01.00 meters & aggregate exit width provided is 01.25 Mtrs

6 OPEN SPACES ALL ROUND BUT

Directions	Open space to be provided as per the G.O. Ms. No. 168, MAUD(M) Department, Dated: 07-04-2012 under Section-7.1 in Table-III	Open spaces Provided by the Builder	Deficit	
NORTH	060035			
EAST	06.00 Mtrs	06.70 Mtrs	Nil	
EAS1	06.00 Mtrs	07.50 Mtrs	Company Services	
WEST		07.30 Mits	Nil	
Ormer	06.00 Mtrs	06.95 Mtrs	Nil	
HTUO	06.00 Mtrs		INII	
	THIS WALLS	06.25 Mtrs	Nil	

7) The minimum Fire Safety Installations required & provided by the builder as per the Table 23 of Part-4 of N.B.C of India 2005.

SI. No	Fire Safety Measures	Required	Provided	. Deficie
١.	Fire Extinguishers as per IS 2190			
2.	Hose Reel	Required	12 No's Provided	Nil
3.	7/1	Required	03 No's Provided	
	Down Comer	Required	03 No's Provided	Nil
4.	Landing Valve With Delivery Hose	Required		Nil
5.	Terrace Tank Of 20,000 Ltrs		03 No's Provided	Nil
6.	Booster Pump 900 LPM	Required	01 Provided	Nil
		Required	01 Provided	
7.	Two Way Fire Brigade Inlet	Required	2.0	Nil
	11	•	· 01 Provided	Nil

- 8) In view of the above, <u>FIRE NO OBJECTION CERTIFICATE</u> for the above said building is issued oject to the following conditions.
- 1. The NOC issued is confined to the fire safety Measures installed in the building and does not confer any legal right for claiming of Ownership of property or conversion of land use / Occupancy or Building Regularization. The Owner / Occupier shall comply the Building Rules / Govt Orders as applicable.
- Fixed and first-aid Fire Fighting equipment, alarm etc shall be tested and maintained regularly as
 per applicable standards and Fire-Drills conducted quarterly for first two years and half yearly
 after two years.
- 3. No temporary structure such as tents or with thatched construction should be allowed for educational institutions.
- 4. The Management shall restrict the occupant load to 120 per floor. If the occupant load increases to more than 140 per floor, an additional staircase of minimum 01.25 mtrs width shall be provided and report compliance.
- The management is advised to provide 20,000 Ltrs of Overhead tank with RCC Construction And report compliance.
- Emergency power generator etc, and associated equipment should be tested periodically, verified as per NBC, and IS-1646.
- Every room with a capacity of 45 students shall be maintained obstruction free minimum two doorways.
- 8. Every vertical opening between at the floors shall be suitably enclose or protected, with ventilation System by ducts and Balconies.
- The Builder / Occupier should facilitate periodical inspection by jurisdiction station Fire Officer and District Fire Officer, Fire Prevention Wing, GHMC, Hyderabad.
- 10. Evacuation plan at showing exit routes and recommended action plan be displayed at conspicuous locations and shall be exhibited all times, all escape /exit routes shall not be blocked or encroached.
 - 11. Fresh NOC would be required for any change in occupancy or additions/alterations in the building structure as per NBC of India and building bye/laws.
 - 12. The Management has to maintain Fire Safety Measures at all times in good working Conditions as seen during the inspection.
 - Any loss of life or property due to Non functioning of Fire Safety Measures and other installation shall be the responsibility of management/owner.
- 14. All the Occupants must know the correct method of operation of the Fire Fighting System Installed.
- All Occupants/ security personnel shall be trained to operate the Fire Safety Equipment during the Emergency.

- 16. Additional/Alteration, if any, in the building may be verified by building authority
- 17. The Fire Drills Shall be conducted once in every Six months for initial two years, thereafter, cace in every 3months.
- 18. This FIRE NO OBJECTION CERTFICATE is valid for Five Years from the date of issue. It is the responsibility of the builder / occupier to apply for renewal of Fire NOC, two months before expiry of this Fire NOC.
- 19. This issuing of Fire NOC without any prejudice to the action taken by GHMC against the Unauthorized construction, if any made.

COMMISSIONER & SPECIAL OFFICER
GHMC, HYDERABAD.

Copies to:

- The Management of M/s. St. Rita High School, FCI-Widia Colony, Miyapur, Serilingampally, Ranga Reddy District.
- 2) The Chief City planner, GHMC, Hyderabad.

Signature valid

Digitally signed by S.DEVENDAR RES Date: 2001,09.15 Reason Advanced

5:40:15 IST

PRINCIPAL
St. RITA HIGH SCHOOL
D.No: 2-3/122, F.C.I. Widia Colony,
Miyapur, Hyderabad-500 049,

For St. RITA EDUCATIONAL SOCIETY

Secretary Correspondent